ESTIMATE

Hyatt Contracting Inc.
3289 ROLLIN HILLS RD
Marysville, CA 95901

accounting@hyattcontractinginc.com
+1 (530) 635-4583
DIR# 1001005498, CSLB# 923900, SB-PW# 2041079

HYATT CONTRACTING INC.
ROCK SOLID COMMITMENT TO QUALITY AND SERVICE

CalFire, Karen Vinciguerra

Bill to
CalFire, BrianSkehan
9471 Browns Valley School Road
Browns Valley, ca 95918

Estimate details
Estimate no.: COO # 13
Estimate date: 10/16/2026

#	Description	Qty	Rate	Amount
1.	Install 4'-8' wide concrete sidewalks at the north and south sides of the fire station wrapping around both sides and tying into existing. Approximately 500 sf of 4" thick 4,000psi concrete. We will grade as needed and install #3 rebar 24" on center each way. Prevailing wages have been included. Project is expected to take 2 days.	1	$18,357.00	$18,357.00

Total **$18,357.00**

Accepted date **Accepted by**